

STRUCTURAL INTEGRITY ASSESSMENT REPORT FOR AN EXISTING THREE BEDROOM SEMI-DETACHED GROUND+1+ROOF PROPERTY





PEARL ENGINEERS PLANNERS AND PROJECT MANAGERS

Name and address of client:

Address of property inspected:

Reference: SIR/2024/03/MT

Weather: Overcast and Cold

Date of Inspection: 12-03-2024

| Doc No. | Date | Rev. | Document Type | Prepared By |
|----------------|--------------|------|---------------|---|
| SIR-2024-03-MT | Marun 202 | C1 | Report | Muhammad Moiz BE CE PGc DM Chartered Building Engineer CBuild E RIBA A. |

Disclaimer:

This report has been prepare the a so beyor merely in their capacity as an employee or agent of a firm, company or other business entity (PEPP). The report is the product of the Company, not of the individual surveyor. All of the statements and opinions contained in this report are excessed a tirely on behalf of the Company, which accepts sole responsibility for them. For their part, the individual surveyor assumes no personal financial responsibility or liability in respect of the report, and no reliance or inference to the contrary should be drawn. This document has been prepared in accordance with the scope of PEPP's appointment with its client and is subject to the terms. What appointment. It is confidential, addressed to and for the sole use and reliance of PEPP's client. PEPP's acceptable liability for any use of this document other than by its client and only for the purposes stated in the document, for which it was prepared an provided. No person other than the client may copy (in whole or in part), use or rely on the contents of this document, who out the prior written permission of a director of PEPP's. Any advice, opinions or recommendations within this document should be read and relied upon only in the context of the document. The contents of this document are not to be construct of providing legal, business or tax advice or opinion.



Table of Content

| 1. | Directives | 4 |
|----|--|-----|
| 2. | Report Analytical Focus | 4 |
| 3. | Scope of the Works | 5 |
| 4. | Comprehensive Overview of the Property | 5 |
| 5. | Narratives (Observation/Causes & Prevent (1) | 6-7 |
| 6. | Causes Prevention and Solutions | 10 |



1. Directives

Upon the instructions received from the client to suspected movement in the external LHS(left hand side) External Brick Wall, Pearl engineers panners and project managers conducted a survey at xxx. To confirm the structural integrity of the property.

2. REPORTS ANALYTICAL FOCUS

This report's scope includes the structural integrity of the property pertaining mainly to the LHS external wall suspected movement, however any other structure-related issues observed are also highlighted. The on-site conditions were being investigated via different non-destructive methods such as, physical, visual and acoustics of the materials

We have not conducted a thorough examination of the woodwork or any concealed areas within the structure, and as such, I cannot verify the absence of defects in the executions of the building.

We appreciate the client's cooperation in granting access to the property as school days and assisting in addressing inquiries raised during our discussions.



3. SCOPE OF WORK

 Conduct a survey to inspect the structural integrity of the 3 Bod Semi Detached Property pertaining to suspected movement of the wall

During the visit dated 12th March 2024, the clients were present to guide us throughout the survey.

4. Comprehensive Overview of the Property.

xxx is a Three-bedroom Semi-Detached Property with a clay tiled pitched roof, and it has a timber flow above. Access to the property is gained through the front entrance door within an open porch. The Property has a Reception room, Breakfast room, and a kitchen on the ground floor. The access to the rear garder has been gained through the kitchen and the breakfast room. The first had has 3 Bedrooms and a full bath. The property has very good loft height bleatance.

The property is raditionally built, where the ground floor is a suspended timber jois floor followed by the first floor and the loft floor, the external walls are mad up of facing bricks with a clay-tiled roof.

There is a garden and a drive in the front of the property and a good-sized garden in the rear.



5. Narratives (Observation/Causes & Prevention).

- The ground floor bay window shows an excessive amount of hoistur content alongside its wall, however, the moisture content is to be rechecked in a few months of duration and if it still show higher levels then a damp proofing course will be installed, although a present it from further increase removing render in the front anternal walls above the DPC course may help.
- Similarly we have noticed damaged gracing along the eaves, any such guttering is to be repaired to avoid any smasher on the external walls. If the wall gets water splashes over the external walls it's very susceptible that incase of any loose pointing it will cause penetrating damp, which is relatively more difficult to identify and resolve.
- 3] The front porch shows historic structural cracks that need to be observed and if incase it's found that they are increasing, then further investigation is required to check for the boundation movement.
- 4] The rear external wails show pointing damages and it's in need of repointing works, therefore it is advised to carry out re-pointing works on the rear external wall.
- The Nichen rear wall along with the utility room shows a very high level or sisture content, whereas damp damage to the finishing is very ovious, the dampness in the kitchen shows signs of rising dampness the reason may include a damaged DPC course. However, a drain pit has been observed exactly at the spot which alarms about any damages in the drain network in the rear of the property. Therefore, before addressing the damp it's advised the drain network should be checked



properly and reinstated, followed by a damp/dry rods treatment.

- Similarly, the external roof tile also shows damages in the front and the rear side of the roof which needs to be addressed in a timely manner avoid any water leaks inside the loft, such leakages may result in structural damage to the roof and loft structure if any leakages found over a period of time.
- The first-floor front room alongside with left elevation shows no signs of crack internally or externally, similarly the left-hand side of the elevation shows no sign of any structural cracks, however, the walls inside the room were found out of plumb and not in a poper right angle, the ceiling of the room is inclined from internal wall to the external wall, as there are no cracks found in the walls, the efort its not attributed to any movement/settlement/subsidence etc.

6. Conclusion:

According to the discharge made above the following recommendation and conclusion has been derived.

"The external LAS shows no signs of settlement/movement or any lean as the client was expecting, the e is no structural cracks have been observed".

There are it my significant aspects that needs to be properly taken care of which are as follow

- The external plaster to be terminated at 50mm below DPC level, and the internal bay win ow walls need to be checked after a period of three months for the moisture concentration.
- The external open porch cracks need to be monitored if there is any increment noted

Pearl Engineers Planners & Project Managers http://Pearlepp.co.uk

Tel.: +442035763199

02 TowerFields Westerham Road BR2 6HF



it should be brought to any structural engineer for assessment.

- All the roofs need to have proper guttering installation, and all the guttering wherever it's damaged to be reinstated to avoid any damage to the existing structure.
- Kitchen rear wall needs a damp roof treatment either dry rods or any injectable reisin that forms an impermeable membrane. However it should be once the drainage network is checked by a proper CCTV survey and if any damages are found ney are reinstated.
- The main pitch roof external roof tiles need to be reinstated to the camages may allow some water to get inside the roof and cause damage of the bit structure and the structure of the roof itself.
- The rear external wall shows pointing damages repointing to be carried out to avoid any further damage.

All the work to be done in a workmanlike making in accordance with CDM2015, where the contractor should ensure proper management and safety during the work.

If in case of any issue, please revert back to the undersigned for further investigation. We hope that this letter series its purpose, however, if you have any questions or concerns, please do not desitate to reach out and contact us at Projects@Pearlepp.co.uk

